


New Bar Timber Roof Layout

Revision note	Mark	Date	By
General Revision	01	26/11/18	SR
<div>Notes</div> <div>1. All Dimensions to be checked on site Prior to execution of works and Any Discrepancies to be reported.</div> <div>2. This drawings shall be read in conjunction with all relevant architectural/MEP drawings and specifications/instructions and any discrepancies shall be reported prior to execution of any works</div> <div>3. Concrete grade shall be 30Mpa at 28 days.</div> <div>4. Lap length shall be 50 times bar diameter. 60 times bar diameter for swimming pool</div> <div>5. Cover to Reinforcement = 50mm to foundations, 30mm to walls and Beams, 40mm for water Retaining Structure. 25mm to slab.</div> <div>6. All Foundation shall be laid on firm stiff soil Free of Magnesium Clay with a Soil bearing capacity of min 125Kpa</div>			
Designed by: SR	Drawn by: SR	Scale:1:75	
<div>Client</div> <div>Long Beach Hotel</div>			
<div>Project</div> <div>New Bar & Timber Decking Adjacent Infinity Pool</div>			
Component Type		Level	
Timber Layout		Roof	
<div>SHAILEN RAMASAMY CONSULTING ENGINEERS LTD</div> <div>Structural & Civil Engineering Services The Hive, Industrial Road, St.Pierre & 48E, Western Boundary, Q-Bornes Tel: 5984-9842 & 460-0000 M.R.P.Eng (Mauritius): Reg No: 1093 VAT No: 27522186</div>			
Date:	Drawing no.	Rev	
Oct 2018	84/L.B/I.P/04	01	