



New Bar Roof Layout

Revision note	Mark	Date	By
General Revision	01	26/11/18	SR

- Notes
1. All Dimensions to be checked on site Prior to execution of works and Any Discrepancies to be reported.
 2. This drawings shall be read in conjunction with all relevant architectural/MEP drawings and specifications/instructions and any discrepancies shall be reported prior to execution of any works
 3. Concrete grade shall be 30Mpa at 28 days.
 4. Lap length shall be 50 times bar diameter. 60 times bar diameter for swimming pool
 5. Cover to Reinforcement = 50mm to foundations, 30mm to walls and Beams, 40mm for water Retaining Structure. 25mm to slab.
 6. All Foundation shall be laid on firm stiff soil Free of Magnesium Clay with a Soil bearing capacity of min 125Kpa

Designed by: SR	Drawn by: SR	Scale:1:75
-----------------	--------------	------------

Client
Long Beach Hotel

Project
New Bar & Timber Decking
Adjacent Infinity Pool

Component Type	Level
Timber Layout	Roof

SHAILEN RAMASAMY
CONSULTING ENGINEERS LTD

Structural & Civil Engineering Services
The Hive, Industrial Road, St.Pierre &
48E, Western Boundary, Q-Bornes
Tel: 5984-9842 & 460-0000
M.R.P.Eng (Mauritius): Reg No: 1093
VAT No: 27522186

Date:	Drawing no.	Rev
Oct 2018	84/L.B/I.P/03	01